


# BADU<sup>®</sup> JET super-sport //

Counter Swimming Unit  
Sistema de Nado Contra Corriente



**SPECK X**  
pumps

## Technical Support:

**Address:** Speck Pumps  
8125 Bayberry Road  
Jacksonville, FL. 32256  
USA

**Hours:** (Monday - Friday) 8:00 am to 5:00 pm EST

**Toll Free:** 800-223-8538

**Phone:** 904-739-2626

**Fax:** 904-737-5261

**Website:** [usa.speck-pumps.com](http://usa.speck-pumps.com)

**Email:** [technical.usa@speck-pumps.com](mailto:technical.usa@speck-pumps.com)

<b>Date of Installation:</b>	
<b>Installed by:</b>	
<b>Serial Number:</b>	
<b>For Service Call:</b>	

*Manufactured by Speck Pumps, Jacksonville Florida USA, ©2023 All Rights Reserved.*

This document is subject to change without notice.

## Safety

Safety is emphasized throughout the user manual. These are safety alert symbols (**CAUTION**, **WARNING**, and **DANGER**). They alert the user of potential personal injury hazards. Obey all safety messages to avoid possible injury or death or damage to equipment.

# Table of Contents

<b>1</b>	<i>Important Safety Instructions</i>	<b>4</b>
	SwimJet Combination Fitting Manufacturers Warnings. . .	4
	General Safety Instructions. . . . .	5
<b>2</b>	<i>General Description</i>	<b>6</b>
<b>3</b>	<i>Installation Information</i>	<b>7</b>
	Receiving Information . . . . .	7
	Plumbing Installation . . . . .	7
	New Concrete or Gunitite Installation . . . . .	9
	Existing Concrete or Gunitite Installation . . . . .	12
	Liner and/or Fiberglass Pool Installation . . . . .	14
	Final Assembly . . . . .	16
	Electrical Installation . . . . .	17
	SPECK Controller . . . . .	18
<b>4</b>	<i>Service and Maintenance</i>	<b>21</b>
	Nozzle Adjustment . . . . .	21
	Winterizing . . . . .	22
<b>5</b>	<i>Frequently Asked Questions</i>	<b>22</b>
	Frequently Asked Questions . . . . .	22
	Troubleshooting . . . . .	23
<b>6</b>	<i>Product Specification</i>	<b>25</b>
	Replacement Parts and Exploded View . . . . .	25
<b>7</b>	<i>Terms &amp; Conditions</i>	<b>27</b>
	Product Registration . . . . .	27
	Limited Warranty . . . . .	27

## Badu® Jet super-sport // Certifications



Complies with UL 1563  
CSA C22.2 No. 218.1-M89  
Swimming Pool Equipment  
Listing #E212148



VGBA 2017

---

# 1 Important Safety Instructions

---

**WARNING:** Before Installing this product, read and follow all warning notices and instructions which are included. Failure to follow safety warnings and instructions can result in severe injury, death, or property damage. Call 1-800-223-8538 or visit [www.usa.speck-pumps.com](http://www.usa.speck-pumps.com) for additional copies of these instructions.

---

## Swim Jet Combination Fitting - Manufacturers Warnings

---

**MUST BE INSTALLED** by an experienced and qualified pool industry professional **ONLY**.

**Attention Installer:** This manual contains important information about installation, operation, and safe use of this product. This information should be given to the owner and/or operator of this equipment. Most Federal, State and Local codes regulate the construction, installation and operation of pools and spas. It is important to comply with these codes, many of which regulate the installation and use of this product.

1. **DO NOT** locate this fitting in seating areas or on the back rests for such seating areas.
2. This fitting should be mounted in the vertical pool wall only per manufacturer's instructions.
3. All fittings and fasteners should be examined for damage or tampering before each use.
4. Any missing, broken, or cracked fittings must be replaced before using this product. Only genuine Speck replacement parts may be used.
5. Acceptable fittings/pipe sizes are listed on page 7 of this manual. No other sizes are permitted.
6. Never exceed the maximum flow rate stated on this product.
7. The anti-entrapment cover must be in place when using this product. **DO NOT** use this product if the cover is missing, broke or loose.
8. The anti-entrapment cover (part# 93.1) should be replaced within 10 years from installation date.
9. Installation requires a Phillips screw driver. All screws should be hand tight only. **DO NOT** use electrical or air drills.
10. Consult your physician before exercising with the Badu® Jet super-sport II or using the massage hose.
11. **DO NOT** permit children to use this product unless they are closely supervised at all times.
12. **DO NOT** remove any safety alert labels such as **DANGER**, **WARNING**, or **CAUTION**. Keep safety alert labels in good condition and replace missing or damaged labels.
13. Stay alert, watch what you are doing and use common sense. **DO NOT** use unit if you are tired and/or exhausted. **DO NOT** use unit while under the influence of drugs, alcohol, or any medications.
14. **CAUTION: DO NOT** increase pump size; this will increase the flow rate through the system and exceed the maximum flow rate stated on this product.

**IMPROPER INSTALLATION OR USE OF THIS PRODUCT MAY PRESENT A RISK OF HAIR OR BODY ENTRAPMENT AND DROWNING.** Install this equipment in accordance with the instructions provided.

---

## Swim Jet Combination Fitting - Manufacturers Warnings - continued

---

*As the manufacturer, Speck Pumps - Pool Products, Inc., hereby certifies that their Swim Jet Combination Fitting meets or exceeds the requirements of the Virginia Graeme Baker Pool & Spa Safety Act, VGBA 2017 and ANSI/APSP 16 standards and safety regulations as set forth by the Consumer Products Safety Commission.*

***“Read, and then keep these instructions for future reference”***

---

### General Safety Instructions

---

The following guidelines provide information to minimize the risk of injury to users of pools, spas, and hot tubs.

**WARNING: TO REDUCE THE RISK OF ENTRAPMENT HAZARD**



*Pool and spa pumps produce high levels of suction, which can pose extreme danger if a person comes in close proximity to an open pool or spa drain or if a drain cover is loose, cracked, broken or missing. Pool and spa pumps move large volumes of water, which can pose extreme danger if a person's hair comes in close proximity to a drain that is not the proper size for the pump or pumps.*

*If not an approved single, unblockable outlet, a minimum of two functioning suction outlets per pump must be installed. Suction outlets in the same plane (i.e. floor or wall) must be installed a minimum of three (3) feet (1 meter) apart, as measured from center point to center point. Dual suction fittings shall not be located on seating areas or on the backrest for such seating areas. If any suction outlets are located closer they shall be located on two different planes (i.e. one on the bottom and one on the vertical wall, or one each on two separate vertical walls).*

**WARNING:** *Failure to keep suction outlet components clear of debris, such as leaves, dirt, hair, paper and other material can result in an increased potential for suction entrapment.*

*If not a single, unblockable outlet, in the event of one suction outlet being completely blocked, the remaining suction outlets serving the system shall have a flow rating capable of the full flow of the pump(s) or the specific suction system. If in doubt about the rating and/or head loss curve of your system, consult a qualified pool or spa professional and/or your respective equipment manufacturer(s). Also, double check with your local building/health authorities regarding single vs. multiple drain installations, etc.*

*Regularly inspect all drain covers for cracks, damage and advanced weathering. If a drain cover becomes loose, cracked, damaged, broken or is missing, close the pool or spa immediately, post a notice and keep the pool or spa closed until an appropriate VGBA 2017 certified drain cover is properly installed.*

### WATER VELOCITY AND FLOW RATES

*The maximum water velocity through drain covers is limited by some local regulations, for example some state health departments limit the velocity through public pool drain covers to 1.5 feet per second. This velocity limit is lower than the flow rating provided by the ANSI/APSP 16 certification; therefore local limit applies and must be followed. Never exceed the flow rating listed on the cover even if local code does not provide a velocity limit.*

*For additional information on proper installation refer to The Association of Pool & Spa Professionals ANSI/APSP-7 Standard and the US Consumer Product Safety Commission Guidelines for Entrapment Hazard.*

---

## General Safety Instructions - continued

---

### VGB Compliance - VIRGINIA GRAEME BAKER POOL AND SPA SAFETY ACT

The Virginia Graeme Baker Pool and Spa Safety Act raises certain new requirements on owners and operators of swimming pools and spas.

Pools or spas constructed on or after December 19, 2008, shall utilize:


- (A) No submerged suction outlets, a gravity drainage system with ANSI/APSP compliant cover(s), one or more unblockable outlets; or
- (B) A multiple main drain system without isolation capability with suction outlet covers that meet ANSI/APSP 16-2011 Suction Fittings for Use in Swimming Pools, Wading Pools, Spas, and Hot Tubs and either:
  - (i) A safety vacuum release system (SVRS) meeting ASME/ANSI A112.19.17 Manufactured Safety Vacuum Release Systems (SVRS) for Residential and Commercial Swimming Pool, Spa, Hot Tub, and Wading Pool Suction Systems and/or ASTM F2387 Standard Specification for Manufactured Safety Vacuum Release Systems (SVRS) for Swimming Pools, Spas and Hot Tubs or
  - (ii) A properly designed and tested suction-limiting vent system or
  - (iii) An automatic pump shut-off system.

Pools and spas constructed prior to December 19, 2008, with a single submerged suction outlet shall use a suction outlet cover that meets ANSI/APSP 16-2011 and either:

- (A) A multiple main drain system without isolation capability, or a single (VGBA 2017 compliant) unblockable suction outlet, or
- (B) A safety vacuum release system (SVRS) meeting ASME/ANSI A112.19.17 and/or ASTM F2387, or
- (C) A properly designed and tested suction-limiting vent system, or
- (D) An automatic pump shut-off system, or
- (E) Disabled submerged outlets, or
- (F) Suction outlets shall be reconfigured into return inlets.

For more information about the Virginia Graeme Baker Pool and Spa Safety Act, contact the Consumer Product Safety Commission at (301) 504-7908 or visit [www.cpsc.gov](http://www.cpsc.gov).

### **WARNING:** Risk of Electrical Shock or Electrocution



*Pool pump must be installed by a licensed or certified electrician or a qualified pool serviceman in accordance with the National Electrical Code and all applicable local codes and ordinances. Improper installation will create an electric hazard which could result in death or serious injury to pool users, installers, or others due to electrical shock, and may also cause damage to property.*

***Always disconnect power to the pool pump at the circuit breaker before servicing the pump. Failure to do so could result in death or serious injury to serviceman, pool users, or others due to electric shock.***

---

## 2 General Description

---

The BaduJet super-sport II from Speck Pumps has been designed to be installed during the construction of your pool to create a water treadmill for anyone wanting a therapeutic and effective exercise. The BaduJet super-sport can be installed in any type of pool, large or small, from gunite to vinyl liner. The self-contained, flush-mounted unit is a jet-propulsion system that pumps water into the pool creating a current in excess of 5,700 gallons per minute from a recessed jet housing. Topping off the experience is the pulsating massage hose which can be attached to the jet nozzles for easy and convenient massage treatments for joints and muscles.

# 3 Installation Information

## Receiving Information

1. Upon receipt of the swimjet system, check the cartons for damage. Open each carton and check the pump, jet housing, anti-entrapment cover, and control box for concealed damage, such as cracks, dents, or a bent base. If damage is found, contact the shipper or distributor where the swimjet was purchased.

2. Inspect the contents of each carton and verify that all parts are included. (See Figure 1)

A. Flush-mount jet housing

B. Rectangular, anti-entrapment cover (20" x 17") for undetectable pump suction.

C. Jet Nozzles

D. Water volume control knob - adjusts the amount of water flow through the jet nozzles

E. Light (ON/OFF) LED push button - turns low voltage LED light ON/OFF.


F. Air regulator knob - adjusts the amount of air bubbles in the water flow

G. System (ON/OFF) push button - turns the swimjet system ON/OFF.

H. Control box complete with GFCI and WiFi control module.

I. Speck Model 21-80/33GS - 4HP, self-priming, single phase plastic pump with built-in thermal overload (no motor starter required). Optional three phase pump and control box also available. (NOTE: Flooded suction pump available for installation below water level)

J. Pulsating massage hose - 5 ft. length



## Plumbing Installation

**CAUTION:** The discharge connection on the back of the jet housing must be located directly **ABOVE** the suction connection.

**CAUTION:** The suction line should remain below water level from the suction connection at the jet housing to a point directly beneath the pump.

**CAUTION:** The center of the BaduJet super-sport nozzles (jet housing center-line) must be located 12" **BELOW** the water line for maximum performance and efficiency.

**CAUTION:** In areas with soft soil conditions or with frequent earth movement, a flexible section of 4" hose should be installed at the back of the jet housing to prevent plumbing or jet housing damage.

**CAUTION:** For trouble-free pump priming (up to 4 feet above the water line), first install a 6" long riser in the discharge connection on top of the pump. Then install an elbow and lead the discharge line downward to the discharge connection at the BaduJet super-sport II jet housing.



## Plumbing Installation - Continued

**CAUTION:** Allow at least 12 hours curing and bonding time. Insufficient curing and bonding time can result in leaks and flooding.

**CAUTION:** Throughout the entire installation, make sure the plumbing connected to the BaduJet super-sport jet housing is well supported. Unsupported plumbing WILL crack the jet housing.

**CAUTION: DO NOT** use the pump as a fixed point (support) for the plumbing.

**CAUTION:** When using 6" pipe, install 6" x 4" reducer bushings at **the jet housing suction and discharge connections.** The 6" suction line should be run from the jet housing and remain under the water line to a point directly beneath the pump. Install a 6" elbow at that point. Then run 4" pipe vertically up to the suction connection of the pump and finish with a 4" elbow.

- For optimal performance, use 4" plumbing when the total distance between the pump and jet housing is 30 ft or less. The plumbing should be as direct and free from turns or bends as possible because **elbows and other fittings can create large friction losses and reduce the performance of the system.** **The shortest length of pipe with the minimum number of fittings possible should be used to avoid any significant friction loss due to the pipe and fittings.** **NOTE:** Refer to Figure 2 for the BaduJet super-sport head loss curve.

- A maximum of seven (7) 90° 4" elbows may be used with 30 ft of horizontal 4" pipe for the suction line and 30 ft of horizontal 4" pipe for the discharge line without negatively affecting the performance of the system.




Figure 2

BaduJet super-sport II Head Loss Curve

- If more elbows are required for the installation, 4" sweeps must be used in place of the elbows. When using sweeps instead of elbows, a maximum of nine (9) 4" sweeps may be used with 30 ft of horizontal 4" pipe for the suction line and 30 ft of horizontal 4" pipe for the discharge line without negatively affecting the performance of the system.
- If the pump cannot be located within 30 ft of the jet housing with the maximum number of 4" elbows or sweeps stated above, then 6" plumbing must be used. For the suction line, use 6" plumbing and fittings from the connection at the jet housing to a point directly beneath the pump. From that point, install a 6" elbow. Then run 4" pipe vertically up to the suction connection of the pump and finish with a 4" elbow. For the discharge line, 6" plumbing should be installed from the discharge connection of the pump all the way to the discharge connection of the jet housing.

**CAUTION:** There is 50 ft. of cable for the push buttons as well as 50 ft. of cable for the LED light included with the BaduJet super-sport II. The control box should be installed within this distance of the jet housing. If a longer distance is required, a junction box can be installed above the water line to splice additional cable as required.

**NOTE:** Suction lines which are too long have significant disadvantages:

- Higher resistance which results in less efficient priming and a higher risk of cavitation.
- Longer priming time (up to 12 min).
- Keep the suction and discharge lines as short and straight as possible.
- If the pump is positioned further away, then the pipe dimensioning has to be adapted so that almost loss-free flowing is ensured.



Figure 3  
Sample BaduJet super-sport // Installation (Self-Priming)

*NOTE: To avoid stress on the housing, the jet housing and 2 to 3 inches of plumbing/conduit stub out may be encased in qunite or concrete.*



9

## Jet Housing Installation - New Concrete or Gunitite Construction

The following is a list of all parts that **ARE NOT USED IN A CONCRETE OR GUNITITE INSTALLATION WITHOUT VINYL LINER:**

- Gasket with knobs (part #26)
- Clamping ring gasket (part #27)
- M8 x 30mm Countersunk Screw (part #98)

### 1. Pre-plumb BaduJet super-sport jet housing:

- Install approximately 12" of 4" SCH 40 pipe to both suction and discharge connections on the back of the jet housing.

*NOTE: If total plumbing length exceeds 30 ft between the jet housing and pump, increase pipe size to 6". Install 6" x 4" reducer couplings at the jet housing connections.*




Image 1  
BaduJet super-sport II pre-plumbed & conduit installed

### 2. Install the protective conduit (refer to Figure 10 on page 14 & Figure 14 on page 16):

- Glue the metric side of the M25 x 3/4" conduit connector (part #118) to protective conduit port on the back of the jet housing.
- Install 3/4" flexible or rigid PVC protective conduit to the 3/4" side of the M25 x 3/4" conduit connector. Run the 3/4" protective conduit to the control box location.

**CAUTION:** There is 50 ft. of cable for the push buttons as well as 50 ft. of cable for the LED light included with the BaduJet super-sport II. The control box should be installed within this distance of the jet housing. If a longer distance is required, a junction box can be installed above the water line to splice additional cable as required.

### 3. Install the air regulator hose (refer to Figure 10 on page 14 & Figure 14 on page 16):

- Glue the metric side of the M20 x 1/2" conduit connector (part #117) to the air regulator port on the back of the jet housing.
- Install 1/2" flexible or rigid PVC conduit (this serves as the air regulator hose) to the 1/2" side of the M20 x 1/2" conduit connector. Run the 1/2" conduit to a point above the water line (for example, at the equipment pad). Install the 1/2" check valve (part #101), O-ring (part #113), and 1/2" conduit adapter (part #116) at the end of the 1/2" conduit.

### 4. For poured concrete pools only:

- Create formwork for the jet housing using Figures 5 & 6.
- Drill the four M8 holes marked (1) in Figure 5 in the formwork for the inner pool wall. Cut a 14.5" hole in the formwork for the outer pool wall. **CAUTION:** The center of the jet housing **MUST BE** mounted 12" **BELOW** the water line as shown in Figures 5 & 6
- Insert the round sealing cord (part #25) in the groove in the back of the jet housing.
- Place the jet housing between the steel rebar with the back of the jet housing against the hole in the outer wall formwork. Jet housing location is very important (See Figure 6).
- Place the gunitite cover (part# 30) on the front of the jet housing. The four (4) holes in the gunitite cover should line up with the holes marked (1) in Figure 5. Tape the edge of the gunitite around the entire jet housing to keep concrete out of threaded inserts and out of the jet housing.
- Place the inner wall formwork on the front of the jet housing, lining up the pre-drilled holes with the holes in the gunitite cover/jet housing. Secure the formwork to the jet housing with four (4) M8 x30 screws (part# 52).

## Jet Housing Installation - New Concrete or Guniting Construction - continued

### 5. For guniting pools:

- Place the guniting cover on the front of the jet housing. Tape the edge of the guniting cover around the entire jet housing to keep guniting out of threaded inserts and out of the jet housing.
- Place the jet housing between the steel rebar. Jet housing location is very important (See Figure 6).

### 6. Pour concrete or apply guniting:

- Front edge of the jet housing should finish even with the finished inside pool wall. Make sure a V shaped groove is scraped out around the housing approximately 1.5" deep to allow marcite to seal against the housing.
- Recheck the location of the jet housing when concrete or guniting is being applied. Make sure the jet housing remains properly aligned and level.
- To avoid stress on the housing, the jet housing and 2 to 3 inches of plumbing/conduit stub out may be encased in guniting or concrete.
- Store all parts not being used now in original box. Store in a safe place until needed.

7. Once the concrete or guniting is fully cured and pool wall is completed, remove the guniting cover. Be sure that the front edge of the jet housing is flush with the pool wall.

**CAUTION:** During plastering, the guniting cover should remain installed on the jet housing.

### 8. Install the clamping ring (part# 28) based on your pool construction:

#### ■ Guniting wall (no tile or liner):

Align the clamping ring (part# 28) then use the twelve (12) M8 x 30 clamping ring screws (part# 52) to attach the clamping ring to the jet housing.

#### ■ Concrete pool with vinyl liner:

Use the provided mounting template (small scale version of template shown in Figure 5) to mark and drill the holes through the liner (twelve (12) M8 clamping ring screw holes and 13.3" center hole). Insert the gasket with knobs in the front of the jet housing (part# 26). Install the liner with the holes aligned to the jet housing. Align clamping ring (part# 28) and place the clamping ring gasket (part# 27) and install using the twelve (12) M8 x 30 clamping ring screws (part# 52). (See Figure 7)




Figure 5  
Installation Template for Concrete or Guniting Pools




Figure 6  
Installation formwork for Concrete or Guniting Pools

---

## Jet Housing Installation - New Concrete or Gunite Construction - continued

---

### ■ Tiled pool:

The tile thickness may be compensated with an additional clamping ring and longer clamping screws (optional parts).  
(See Figure 8)




Figure 7  
Installation for concrete pool with a vinyl liner




Figure 8  
Installation for a tile pool

---

## Jet Housing Installation - Existing Concrete or Gunite Construction

---

Materials: (*NOT INCLUDED*)

- One (1) piece of plywood 2' x 3' x 1/4"
- Eight (8) Lag screws 1/4" x 1-1/2" (minimum)
- Eight (8) Plastic lag shield anchors

1. Follow steps 1-4 under Jet Housing Installation - New Concrete or Gunite Construction on pages 9 - 10.

2. Carefully, choose the location where the BaduJet super-sport will be installed; it should be a flat surface with no or very little crown.

---

## Jet Housing Installation - Existing Concrete or Guniting Construction - continued

---

3. Using a concrete saw, cut out the outline of the section to be chiseled out with an air hammer or equal. This hole should be 19" wide by 19" **BELOW** the water line. The bonding rods on the cap of the pool should be left intact, while all other steel rods should be cut back to clear the placement of the jet housing.

4. Taking the 2' x 3' x 1/4" plywood, set its top edge even to the cap of the pool wall. In some cases a larger piece of plywood maybe needed to cover the hole completely. If plywood covers the hole completely, mark the water line on the plywood. From this line, layout and drill holes in plywood for the four (4) M8 x 30 screws (part #52) for gunite cover, and the eight (8) 1/4" lag screws. (See Figure 9)

5. Place gunite cover on the front of the jet housing. The four holes should be lined up with the holes marked (1) in Figure 5. Tape the edge of the gunite cover around the entire jet housing to keep gunite out of threaded inserts and out of the jet housing. Next place plywood on the front of the jet housing and secure to four (4) M8 x 30 screws (part #52). The discharge connection should be located directly **ABOVE** the suction connection.

6. Now place this assembly into position in the pool wall and align the water line marks. With a level on the two (2) horizontal studs, level the assembly and mark the eight (8) holes for the 1/4" lag shield anchors. Remove assembly and drill holes for lag anchors. Install lag shield anchors. Reposition the assembly and secure it to the lag shield anchors with 1/4" lag screws. It is best to check with a level before tightening the lags down. Back fill and form the outside of pool wall.

7. Mix compound that is compatible and has a good bonding characteristics to the pool wall compound. Pour mixture into form. Use a mallet and lightly tap the front of formed assembly to settle mixture, and avoid any air bubbles in the pour. It should be filled to the top of the plywood. Let mix cure and then remove plywood from the housing assembly. Leave gunite cover installed until pool wall is complete. Drill out plastic lag anchors and fill in the holes. Apply finish to pool wall (plaster, tile, paint, etc.). Remove the gunite cover and gasket with knobs.

*NOTE: To avoid stress on the housing, the jet housing and 2 to 3 inches of plumbing stub out may be encased with gunite or concrete.*

8. Install the clamping ring (part# 28) based on your pool type:

■ **Gunite wall (no tile or liner):**

Align the clamping ring (part# 28) then using the twelve (12) M8 x 30 clamping ring screws (part# 52), attach the clamping ring and handles to the jet housing.

■ **For a concrete pool with vinyl liner:**

Use the template in Figure 5 to mark and drill the holes through the liner (twelve (12) M8 holes and center 14" hole). Insert the gasket with knobs (part# 26) in the front of the jet housing. Install the liner with the holes aligned with the jet housing. Install the clamping ring (part# 28) and clamping ring gasket (part# 27) using the twelve (12) M8 x 30 clamping ring screws. (See Figure 7)

■ **In a tiled pool:**

The tile thickness may be compensated with an additional clamping ring and longer clamping ring screws (optional parts). (See Figure 8)

9. Continue to Final Assembly Section on page 16.

## Jet Housing Installation - Existing Concrete or Gunite Installation - continued




Figure 9  
Layout for installing in existing gunite or concrete pools

## Jet Housing Installation - Liner and/or Fiberglass Pool Construction

**CAUTION:** Locate discharge connector directly **ABOVE** the suction connection. Discharge and suction connectors must be exactly vertical or the stainless steel handles will not align properly. (See Figure 10)

**CAUTION:** Center of the jet housing (the two jet nozzles) should be exactly 12" **BELOW** water level for maximum efficiency.

**CAUTION:** Gasket with knobs (part# 26) goes **BEHIND** pool wall.

**CAUTION:** Clamping ring gasket (part# 27) goes in **FRONT** of pool wall. A good RTV silicone may be used with gasket when mounting jet housing, but in most cases it is not necessary. Installer should decide whether or not silicone is necessary.

1. Cut 13.3" hole through pool wall. Ensure that the center of this hole is 12" **BELOW** the water level.

2. Using the template shown in Figure 11, mark and drill the fourteen (14) M8 holes through the pool wall.

3. Insert the gasket with knobs (part# 26) in the front of the jet housing. Align the jet housing on the outside pool wall, making sure the discharge connector is directly **ABOVE** the suction connector.

4. **For Liner pools only:** Install the two M8 x 30 countersunk screws (part# 98) in the two holes at 15° from the vertical axis. This will keep the jet housing attached to the pool wall for liner installation and replacement.

5. Align the clamping ring gasket (part# 27) on the inside of the pool wall (or on liner) as shown in Figures 12 & 13. Be sure the ribs on the outer edge of the gasket are facing away from the pool wall and are positioned as shown.




Figure 10  
Jet Housing - Rear View



## Jet Housing Installation - Liner and/or Fiberglass Pool Construction - continued

6. Align the clamping ring (part# 28) over the clamping ring gasket (part#27).

7. Install the twelve (12) M8 x 30 clamping ring screws (part# 52).

8. Follow steps 1-4 under Jet Housing Installation - New Gunite or Concrete Construction on page 9 - 10.

9. Continue to Final Assembly Section on page 16.

**NOTE:** The gunite cover (part# 30) is used in those cases where the swimming pool is commissioned without the final assembly kit being installed.

**CAUTION:** All screws should be **HAND TIGHT. DO NOT** use drills or pneumatic tools. **DO NOT** over tighten!




Figure 11  
Template for fiberglass/vinyl liner pools




Figure 12  
Fiberglass Pool Installation




Figure 13  
Liner Pool Installation



## Final Assembly

1. Insert the o-ring (part# 62) in the jet housing as shown in Figure 14.

2. Start the ten (10) nozzle housing tapping screws (part# 61) into the pre-assembled nozzle housing (part# 102.1). Place the nozzle housing at the main jet housing.

3. Route the LED push button cables through the button openings of the nozzle housing.

**NOTE: Light ON/OFF button is on the left and the pump ON/OFF button is on the right**

4. Slide one (1) o-ring (part# 37) onto each push button. Insert the two (2) push buttons into the nozzle housing and lock them by turning them clockwise until they 'click' into place.

5. Feed cables for both push buttons and LED light through the protective conduit as shown in Figure 14. Allow enough cable to reach the control box. Excess can be trimmed upon installation. Mark the end of each button cable with a marker. (P = Pump & L = Light.)

6. Fasten the internal air regulator hose (part# 4) to the hose nipple inside the jet housing using the hose clamp (part #9).




Figure 14

7. Align the complete nozzle housing to the main jet housing and fasten the ten (10) pre-assembled tapping screws. All screws should be **HAND TIGHT**. **DO NOT** use drills or pneumatic tools. **DO NOT** over tighten!

8. Place the rectangular cover (part# 93) against the clamping ring (part #28) and fasten with four (4) 8.4mm washers (part# 94) and four (4) M8 x 20 machine screws (part# 95) and cover the openings with the rectangular covers (part# 96). All screws should be **HAND TIGHT**. **DO NOT** use drills or pneumatic tools. **DO NOT** over tighten! Make sure the UP label is in the correct position.

**WARNING: DO NOT** use or operate the BaduJet super-sport II if the anti-entrapment cover is missing, broken, or loose.

9. Align the light cover (part# 110) with the nozzle housing and secure with four (4) light cover tapping screws (part# 112). (See Figure 15)

**NOTE: Light ON/OFF button is on the left and the pump ON/OFF button is on the right.**

10. Mount the volume control knob (part #21.1) and air regulator knob (part #111) by means of a rubber mallet and a protective cloth. (See Figure 16)

## Final Assembly - continued




Figure 15  
Installation of Light Cover




Figure 16  
Installation of Knobs

## Electrical Installation

**WARNING:** The wiring of the pool motor and control box should be done by a licensed electrician in accordance with all local, state, and federal codes. Be certain that the motor frame and control box are grounded. Motor name plate has voltage, phase, amp draw, and other motor information as well as wiring connection instructions.

This section concerns the electric motor, control box, and metal parts of the BaduJet super-sport.

**CAUTION:** Before installing the Speck Pump, read the entire pump owner's manual found in the pump box.

Consult local codes for minimum distance between pump and pool. Locate pump as close to the pool as practical.

**CAUTION:** There is 50 ft. of cable for the push buttons as well as 50 ft. of cable for the LED light included with the BaduJet super-sport II. The control box should be installed within this distance of the jet housing. If a longer distance is required, a junction box can be installed above the water line to splice additional cable as required.

**BONDING:** As required by the National Electrical Code, the electric pump motor must be electrically bonded to the pool structure (reinforced bars, etc.) by a solid copper conductor not smaller than No. 8 AWG. Bonding lugs are provided on the electric pump motor.

**GROUNDING:** Permanently ground the pump motor and control box using a conductor of appropriate size.

- Pump Motor: Connect to the No. 10 green headed ground screw provided inside the motor terminal box.
- Control Box: Connect to the aluminum grounding terminal strip on the inside of the control box enclosure.

**CAUTION: DO NOT** connect to electric power supply until the unit is permanently grounded.

## SPECK Controller


### Connecting the SPECK controller to a WiFi network for the FIRST TIME:

1. Before connecting the SPECK controller to the WiFi network, stand where the SPECK equipment is located and with your mobile device in-hand assure that the signal strength to the WiFi network is good to excellent (*weak signals will cause problems*).
2. Make sure the power to the SPECK Device is turned ON. There is a green indicator on the controller board to indicate power. A small "o" will be flashing on the LED display.
3. Give the homeowner the BADUConnect app manual and allow them to finish the App setup. *For more information, Call 800-223-8538 or visit [www.usa.speck-pumps.com](http://www.usa.speck-pumps.com) for additional copies of the BADUConnect App instructions.*


Table 1 - LED Push Button Color Codes

COLOR	MEANING
Solid BLUE	SwimJet System is OFF
Solid GREEN	Light is ON
Flashing GREEN every 1 second	SwimJet System is ON with 2 hour timer
Flashing GREEN every 1/2 second	This is a 2 minute warning on the 2 hour timer. Once the 2 minutes have passed the swimjet system will automatically turn OFF.
Flashing RED (Light button only)	LED Light Error

Figure 17  
Control Box Wiring



## SPECK Controller - continued



## SPECK Controller - continued

Table 2  
LED Codes & Meanings

PATTERN ON LED DISPLAY	CONDITION
Flashing Dash (-) with an interval of ~200ms	Ideal with no Relay/Pump on
Flashing 'P' with the interval of ~200ms	No WiFi connection, Wrong Wifi Password
Flashing 'O' (Capital O) with an interval of ~200ms	No cloud connection due to server down or no Internet
Flashing 'o' (Small o) with an interval of 200ms	Device has not been set up to connect to WiFi
Flashing '≡' (triple bars) with an interval of 200ms	The device is doing OTA Firmware update
Flashing 'E' with an interval of ~200ms	Hardware error
Flashing 'L' with an interval of ~200ms	Pool light error
Steady 2	Port 2 is on manually (No Timer/Schedule)
Steady 3	Port 3 is on manually (No Timer/Schedule)
Steady 4	Port 4 is on manually (No Timer/Schedule)
Steady 5	Port 5 is on manually (No Timer/Schedule)
Steady 1 with flashing dot. The dot will flash with an interval of ~100ms	Port 1 is on a schedule based on Time of Day.
Steady 2 with flashing dot. The dot will flash with an interval of ~100ms	Port 2 is on a schedule based on Time of Day.
Steady 3 with flashing dot. The dot will flash with an interval of ~100ms	Port 3 is on a schedule based on Time of Day.
Steady 4 with flashing dot. The dot will flash with an interval of ~100ms	Port 4 is on a schedule based on Time of Day.
Steady 5 with flashing dot. The dot will flash with an interval of ~100ms	Port 5 is on a schedule based on Time of Day.
Flashing 1 with the interval of ~100ms	Port 1 is on a countdown timer
Flashing 2 with the interval of ~100ms	Port 2 is on a countdown timer
Flashing 3 with the interval of ~100ms	Port 3 is on a countdown timer
Flashing 4 with the interval of ~100ms	Port 4 is on a countdown timer
Flashing 5 with the interval of ~100ms	Port 5 is on a countdown timer
Blue light is ON	LED Push Button: When Port 1 or 2 is OFF
Green-light is ON	LED Push Button: When Port 2 is ON in manual mode
Green light is Flashing 1 second interval flashing when time remaining is more than 2 minutes otherwise flashes with 0.5 second	LED Push Button: When Port 1 or 2 is ON in Timer or scheduler mode
Red light is flashing	LED Push Button: When there is an error with the Swimjet Light (Port 2)

# 4 Service and Maintenance

## Nozzle Adjustments

Each BaduJet System is provided with a set of nozzle adjustment tools. These tools will allow the user to set the jet nozzles into position for optimum performance.

When setting the nozzles for basic swimming, it is recommended that you set the nozzles in such a way that each nozzle intersects 4 feet away while breaking the surface at the same time. To help set the nozzles in position for best performance, please follow these instructions:

1. Extend the nozzle adjustment tool to full length.
2. Place each nozzle adjustment tool into the jet nozzles on the BaduJet housing.
3. Once that is complete, bring the blue nozzle tool up to where the end of the nozzle tool breaks the surface of the water. Then bring the two nozzles tools together to meet. (See Figure 19)



Figure 18  
Nozzle Adjustment Tools

*NOTE: Though the nozzle adjustment tools are designed for outdoor use, it is advised to protect them from continuous direct heat.*




Figure 19  
BaduJet Nozzle Adjustment

---

## Winterizing

---

*In areas subject to freezing water temperatures, you should protect your equipment. We recommend you purchase a winter cover kit part #2326000010K. This kit includes one (1) winter plate, one (1) gasket, four (4) M8 washers, and four (4) M8 x 30mm screws. (See Figure 20)*

Also, you can protect your swimjet system as follows: Drain pool until water level has dropped below the anti-entrapment cover. (See Figure 21) Then protect pump by removing drain plug and red filler plug (if applicable).




Figure 20  
Winter Cover Kit




Figure 21

---

# 5 Frequently Asked Questions

---

## Frequently Asked Questions

---

### **What size pool do I need?**

The BaduJet super-sport can be installed in any size pool. However, we recommend a minimum length of 14' and a minimum width of a 7 ft. swimming lane.

### **What size plumbing is necessary? How far away from the BaduJet super-sport can the pump be installed?**

Use 4" plumbing up to 30 ft.. For runs longer than 30 ft. use 6" plumbing. The pump should be placed as close to the BaduJet super-sport as local codes will allow. See plumbing installation on page 7 for more details.

### **How many amps does the pump operate at?**

4.0 HP: Maximum 21.0 - 19.4 Amps @ 208-230 V

### **What size breaker do I need?**

You must use a 40 amp breaker for the 4 HP pump to avoid nuisance tripping.

### **Is the BaduJet Super-sport approved?**

Yes. The BaduJet Super-sport swim jet system is listed by MET and complies with ASME standard ANSI/ASME A112.19.8 (ANSI/APSP-16, 2011) Standard for Swim Jet Combination Fittings, and is VGB 2008 compliant.



---

## Frequently Asked Questions - continued

---

### Does the LED light come in different colors?

Yes. The LED light comes in blue or a multi-color option.

### Does it matter if the housing is installed higher or lower than the manual states?

Yes, the center of the jet must be 12" **BELOW** estimated water level for proper performance of unit. If installed too high, the pump will draw in air from the top of the water level. If installed too low, a good swim lane cannot be developed.

### Can the pump be placed below water level?

Yes. However, for best performance we recommend ordering a pump for flooded suction (Model 21-80/33G) instead of self-priming (Model 21-80/33GS). We recommend installing valves when installing below water level for ease of maintenance.

### Do I need to install a motor starter?

In most cases, no. All single phase pumps have built-in thermal overloads. Also, the three phase Model 21-80/33 has built-in thermal overload. Other three phase pumps require a motor starter.

### Should the swimjet system be tied into the filter system?

No. The swim jet system and the filter system should not be plumbed together as they each provide very specific functions.

### Can I use it with automated controls?

Yes. It comes with the ability to tie into automated control systems or other switching devices.

---

## Trouble Shooting

---


PROBLEM	POSSIBLE CAUSES	SOLUTION
1. Pump will not prime.	a. Suction air leak.	Make sure the red filler plug and o-ring are clean and properly positioned. Tighten red filler plug. Tighten all pipes and fittings on suction side of the pump. Be sure water in the pool is high enough to flow through the jet housing.
	b. No water in pump.	Make sure pump housing is full of water.
	c. Closed valves or blocked lines.	Open all valves in system. Open pump and check for clogging of impeller.
	d. Low voltage to motor.	Check voltage at motor. If low, pump will not come up to speed.
2. Motor does not turn.	a. No power to motor.	Check that all power switches are on. Be sure fuse or circuit breaker is properly set. Check motor wiring at terminals.
	b. Pump jammed.	With power off, turn shaft. It should spin freely. If not, disassemble and repair.
3. Low flow.	a. No water in pump.	See problem 1.
	b. Closed valves or blocked lines.	
	c. Low voltage to motor	
4. Noisy operation of motor.	a. Bad bearings.	Check for noise when shaft is turned by hand. Motor will be very hot in bearing area when running. Replace bearing.

## Trouble Shooting - continued

PROBLEM	POSSIBLE CAUSES	SOLUTION
5. Motor runs hot.	These motors will run hot to the touch, however, this is normal. They are designed that way. Thermal overload protector will function to turn them off if there is an overload or high temperature problem. Excessive heat can be caused by:	
	a. Low voltage.	Increase size of electrical wire. Be sure motor is operating on correct voltage.
	b. Installed in direct sun.	Shield motor from sun's rays.
	c. Poor ventilation.	<b>DO NOT</b> block motor ventilation openings.
6. Noisy operation of pump.	a. Air leak in suction line.	Repair leak. Check suction pipe, red filler plug, and o-ring (See Problem 1).
	b. Restricted suction line due to blockage or under size pipe. Indicated by high vacuum reading at pump suction.	Remove blockage or increase suction pipe size. Are all suction valves fully open?
	c. Foreign matter (gravel, metal, etc.) in pump impeller.	Disassemble pump and remove foreign matter from impeller.
	d. Cavitation.	Improve suction conditions. (Reduce suction line length, reduce number of fittings, increase pipe size.)
7. Motor overload protection "kicks out".	a. Motor is not connected properly.	Check wiring diagram on motor.
	b. Low voltage due to under size wire or low incoming voltage.	Check with volt meter. Increase size of supply wire. Report low supply voltage to power company. Voltage at motor must be within 10% of motor nameplate voltage.
	c. Wrong size heaters in protective device.	Heaters should be one size larger than full load amps shown on motor nameplate.
	d. Overload due to binding in pump or wrong size impeller.	Indicated by high amperage readings on motor, binding shaft. Disassemble unit and correct.
8. The LED light is not working?	a. Control Box.	Contact certified electrician to diagnose control box components.
9. The volume control knob keeps spinning?	a. Broken Spindle.	Contact the factory 800-223-8538
10. My ON/OFF LED push button is not working properly?	a. Control Box.	Check GFCI. If green LED does not stay ON, contact a certified electrician to diagnose control box components.
11. The system will not turn OFF?	a. Control Box Components.	Press TEST button on the control box GFCI to turn off system. Contact a certified electrician to diagnose control box components.
12. I have the volume control knob turned completely up but the flow is weak?	a. Debris in pump casing/impeller.	Check inside pump casing for any debris.
	b. Improper swim jet assembly.	The internals may need to be removed for inspection of the spindle.

# 6 Product Specification

## Replacement Parts



## Replacement Parts

Order#	Drawing #	Qty Required	Description
2326000002A	1	1	Jet Housing
2301001007	4	1	Hose - Air Regulator 8 x 3mm (Price Per Foot - Needed 3 Ft.)
2326000408	6	1	Hose (3x) With Y-Hose Barb
2301001008	9	2	Clamp - Hose, Air Regulator 14/9 SS A4
2326000031	20	1	Strain Relief - Light Cable, 3/4" NPT
2321000409	21	1	Air Regulator Complete
2326000006	21.1	1	Volume Control Knob
5879812995	22	3	Screw - Air Regulator, 2.9 x 9.5 A4
5882501619	23	1	Strain Relief - Light Cable, M16 x 1.5
2326000020	25	1	Round Sealing Cord
2301000026	26	1	Gasket With Knobs - Jet Housing
2326000021	27	1	Gasket - Clamping Ring
2301000028	28	1	Ring - Clamp
2301000030K	30-33	1	Gunite Cover Kit
2326000014	37	2	O-ring - Push Button - 24 x 3mm
2336002899A	38.1	1	50 ft. LED Push Button CPL - Pump
2336002898A	38.2	1	50 ft. LED Push Button CPL - Light
5879860830	52	12	Screw - Clamping Ring, Pozidriv/ Pan M8 x 30mm A4
2302002954	54	2	Nozzle - 40mm
2302002056	56	2	Seat - Nozzle
2302002057	58	2	Spacer - Nozzle 6.2mm
2319800817	59	2	Nozzle Flange
5879006023	60	6	Tapping Screw - Ball Nozzle Flange, 6 x 22mm A4
5879006023	61	10	Tapping Screw - Nozzle Housing, 6 x 22mm A4
2326000013	62	1	O-ring - Nozzle Housing 257 x 3mm
2326000004	63	1	Volume Control
2302002964	64	1	Volume Control Spindle CPL
2302002065	66	2	Washer - Volume Control Spindle, 23 x 16.2 x 1.5mm
2302002067	67	1	Retainer - Shaft, Volume Control Spindle
2302005236	93	1	Cover - Rectangular
5871250800	94	4	Washer - Rectangular Cover 8.4mm A4
5879860820	95	4	Bolt - Rectangular Cover, Phillips M8 x 20mm
5879850880	95.1	4	Bolt - Rectangular Cover, Phillips M8 x 80mm
2302005237	96	4	Plug - Rectangular Cover
2991000140	98	2	Screws - Countersunk Phillips M8 x 30mm
5030000105	101	1	Valve - Check 1/2"

Order#	Drawing #	Qty Required	Description
2326000003	102	1	Housing - Nozzle
2326000401K	102.1	1	Housing - Nozzle Complete w/ LED Light
3932541201	107	1	O-ring - Light 48 x 2mm
2607101019	108	1	O-ring - Light 49 x 3.5mm
2326000057	109	1	Light LED 12V AC - White, 15m
2326000035	110	1	Light Cover
2321000022	111	1	Air Regulator Knob
5879006023	112	4	Tapping Screw - Light Cover, 6 x 22mm A4
2920141230	113	1	O-ring - Check Valve, 19 x 3mm
2326000032	114	1	O-ring - Strain Relief
2326000034	115	1	Adaptor - Strain Relief, Female, PVC 3/4"
2301001030	116	1	Adaptor - Check Valve, Male, PVC 1/2"
5862432021	117	1	Connector - Air Regulation Line M20 x 1/2"
5862432531	118	1	Connector - Conduit M25 x 3/4"
2920280740	Not Shown	1	Control Box - BJC-7-GFCI-WIFI+CPB

### Parts Below Are Unique to the BaduJet super-sport II Shipped Prior to 11/2019

2326000014	37	2	O-ring - Pneumatic Button 24 x 3mm
2321000401	38.1	1	Pneumatic Button CPL - Pump
2321000404	38.2	1	Pneumatic Button CPL - Lights
2300202060	47	2	Air Tubing - Light/Pump 4 x 1.5mm (Price Per 10m)
2302001046	48	2	Clamp - Hose, Pneumatic Button 6.8 - 8mm

### Optional Parts

2326000036	109.1	1	Light LED 12V AC - Multi-color, 10m
2326000049	109.2	1	Light LED 12V AC - Blue, 15m
2326000010K	Not Shown	1	Winter Cover Kit
2300022010	Not Shown	1	Cap - Nozzle & Hand Grip, Close Off
2300003010	Not Shown	1	Massage Hose 5 ft. w/Pulsator & Hand Grip
2300003310	Not Shown	1	Massage Hose 15 ft. w/ Pulsator & Hand Grip
2308799007	31	1	Kit - Nozzle Adjustment Tool
2336002899B	38.1	1	100 ft. LED Push Button CPL - Pump
2336002898B	38.2	1	100 ft. LED Push Button CPL - Light

# 7 Terms & Conditions

## Product Registration

Thank you for purchasing a SPECK PUMPS® product please take a few moments to register it online. Your registration helps us keep you up to date on product information and offers.

### Before you register:

What do I need to get started?

- The Serial Number and the Model Name
- An email address. We will use this to send you confirmation of your registration.
- A copy of your sales receipt and/or qualified installer's invoice.

To register your SPECK equipment please register online at [www.usa.speck-pumps.com/register/](http://www.usa.speck-pumps.com/register/)

or

Scan QR code to register product



## Limited Warranty

Speck Pumps-Pool Products, Inc. grants solely to the original consumer purchaser ("Buyer") of the BADU® SwimJet System(s) the following personal, non-transferable and limited warranty on the following terms and conditions (the "Limited Warranty"): the BADU SwimJet System(s) is warranted to be free of material defects in materials or workmanship under normal use for a period of one (1) year beginning on the date of the Buyer's purchase of the BADU SwimJet System(s) (the "Limited Warranty Period"). Notwithstanding any provisions herein to the contrary, the warranties and obligations hereunder shall not in any event extend for more than two (2) years beyond the date of shipment of the BADU SwimJet System(s) from the factory (the "Limited Warranty Period"). The Limited Warranty is subject to each of the following additional terms and conditions:

**1. IN THE EVENT OF ANY BREACH OF THE LIMITED WARRANTY, SPECK PUMPS-POOL PRODUCTS, INC.'S ENTIRE OBLIGATION AND LIABILITY TO BUYER, AND BUYER'S SOLE AND EXCLUSIVE REMEDY SHALL BE AS FOLLOWS:** Speck Pumps-Pool Products, Inc. will, at its option, either repair or replace the BADU SwimJet System(s) or refund to Buyer the purchase price actually paid by Buyer for the BADU SwimJet System(s) subject to the Limited Warranty. Speck Pumps-Pool Products, Inc. shall have no obligations under the Limited Warranty unless Buyer delivers timely written notice to Speck Pumps-Pool Products, Inc. of the Limited Warranty claim within the Limited Warranty Period and returns the BADU SwimJet System(s) to Speck Pumps-Pool Products, Inc. if requested. To the fullest extent permitted by law, Speck Pumps-Pool Products, Inc. expressly disclaims any liability for, and the Limited Warranty does not include or cover, any labor, costs or other expenses in connection with the removal, transportation, shipment, insurance, replacement, repair, or installation of repaired or replaced parts or for any other costs or expenses or damages to property or things including, but not limited to, those arising in connection with the use of, or inability to use, the BADU SwimJet System(s).

2. To the fullest extent permitted by law, the Limited Warranty will be void and of no force or effect and Speck Pumps-Pool Products, Inc. will have no liability, responsibilities or obligations to Buyer or with respect to the BADU SwimJet System(s) in the event of the occurrence of any one or more of the following:

- Any damage to the BADU SwimJet System(s) caused by Buyer, any third party, ground movement, other natural forces, acts of God or any other sources or causes not arising from a breach of the Limited Warranty, excluding ordinary wear and tear;
- Any replacement, modification, alteration or repair of any parts or components of the BADU SwimJet System(s) by anyone other than Speck Pumps-Pool Products, Inc.;
- Any abuse, misuse, accident, tampering with, improper installation or modification of the BADU SwimJet System(s) or any other actions, inactions or failures to act that violate the terms and conditions of this Limited Warranty;
- Buyer's failure or inability to present an invoice, bill, receipt or other documentation clearly evidencing that the BADU SwimJet System(s) was installed and maintained in strict compliance with this Limited Warranty and that the claim was timely submitted within the Limited Warranty Period; and/or
- Buyer's failure to comply with the conditions and contingencies set forth in paragraph 3 below.

3. The Limited Warranty is expressly conditioned and contingent upon Buyer's strict compliance with each of the following:

- Installation of the BADU SwimJet System(s) by an experienced and qualified pool industry professional and a licensed electrician who is licensed within the jurisdiction in which the BADU SwimJet System(s) is installed and will be used; and

---

## Limited Warranty - continued

---

- (b) Buyer's operation and maintenance of the BADU SwimJet System(s) in strict accordance with Speck Pumps-Pool Products, Inc.'s printed operator/maintenance manuals delivered with the BADU SwimJet System(s).

**4. DISCLAIMER: THE LIMITED WARRANTY IS THE ONLY WARRANTY MADE AND IS IN LIEU OF ALL OTHER WARRANTIES, AND ANY AND ALL IMPLIED WARRANTY OR CONDITION OF MERCHANTABILITY, THE IMPLIED WARRANTY AGAINST INFRINGEMENT, AND THE IMPLIED WARRANTY OR CONDITION OF FITNESS FOR A PARTICULAR PURPOSE ARE EXPRESSLY LIMITED IN THEIR SCOPE AND DURATION TO THE ONE YEAR TERM OF THE LIMITED WARRANTY SET FORTH HEREIN. SOME STATES DO NOT ALLOW LIMITATIONS ON HOW LONG AN IMPLIED WARRANTY LASTS, SO THE ABOVE LIMITATION MAY NOT APPLY TO THE BUYER.**

**5. TO THE FULLEST EXTENT PERMITTED BY LAW, IN NO EVENT SHALL SPECK PUMPS-POOL PRODUCTS, INC. OR ITS OFFICERS, DIRECTORS, EMPLOYEES, SHAREHOLDERS, AGENTS, OR REPRESENTATIVES BE LIABLE FOR ANY SPECIAL, INDIRECT, INCIDENTAL, EXEMPLARY OR CONSEQUENTIAL DAMAGES OR LOSS, INCLUDING TIME, MONEY, GOODWILL, AND LOST PROFITS IN ANY WAY WHICH MAY ARISE HEREUNDER OR FROM THE USE OF OR INABILITY TO USE THE BADU SWIMJET SYSTEM(S) OR THE PERFORMANCE OR NONPERFORMANCE OF ANY OBLIGATION UNDER THIS LIMITED WARRANTY. THIS PARAGRAPH, THE WARRANTY DISCLAIMERS IN PARAGRAPH 4 ABOVE, AND THE SOLE AND EXCLUSIVE REMEDY SET FORTH IN PARAGRAPH 1 ABOVE SHALL APPLY EVEN IF SPECK PUMPS-POOL PRODUCTS, INC. HAS BEEN NOTIFIED OF THE POSSIBILITY OR LIKELIHOOD OF SUCH DAMAGES OCCURRING, WHETHER SUCH LIABILITY IS BASED ON CONTRACT, TORT, NEGLIGENCE, STRICT LIABILITY, PRODUCTS LIABILITY OR OTHERWISE, AND EVEN IF ANY REMEDY STATED HEREIN FAILS OF ITS ESSENTIAL PURPOSE. SOME STATES DO NOT ALLOW THE EXCLUSION OR LIMITATION OF SPECIAL, INDIRECT, INCIDENTAL, EXEMPLARY OR CONSEQUENTIAL DAMAGES OR LOSS, SO THE ABOVE EXCLUSIONS AND LIMITATIONS MAY NOT APPLY.**

6. This Limited Warranty gives the Buyer specific legal rights, and the Buyer may also have other rights, which vary from state to state.

7. A return merchandise authorization ("RMA") must be obtained from Speck Pumps-Pool Products, Inc. before returning any product. Products returned without an RMA will be refused and returned, unopened, to the Buyer. All returned products are to be sent freight prepaid and insured for Buyer's protection to the manufacturer at 8125 Bayberry Road, Jacksonville, Florida 32256 USA. Under no condition will products be accepted after the expiration of the Limited Warranty Period. Speck Pumps-Pool Products, Inc. shall not bear any costs or risks incurred by Buyer in shipping a defective BADU SwimJet System(s) to Speck Pumps-Pool Products, Inc. or in shipping a repaired or replaced BADU SwimJet System(s) to Buyer.





